

## KADUR DIVISION.

## ADVERTISEMENT.

The 10th April 1892.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 30th April 1892, for restoring Koranhalli Heroyettinkere Tank, Tarikere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1893.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Koranhalli Heroyettinkere Tank, Tarikere Taluk;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

RESTORING KORANHALLI HEROYETTINKERE, REGISTERED NO. 458 OF TARIKERE TALUK.

Items of Work.		Per.	Quantity.	Rate.	
				Rs.	A. P.
<b>Bund—</b>					
Earthwork watering and tamping (great lead & lift)	..	C. Yd.	50,649		
Rough stone work, new (high lift)	..	Do	3,348		
Do old	..	Do	50		
Grade stone	..	Each.	20		
B. M. stones	..	Do	2		
Gauge stones including carting and cutting figures	..	Sq. Ft.	60		
<b>Sluice—</b>					
Burnt brick in mortar	..	C. Ft.	804		
Burnt stone slabs	..	S. Ft.	273		
Gibbet stones, bottom and top orifices stones and plug, &c., complete	..	Lump Sum.	..		
Plastering with chunam	..	Sqr.	3-27		
<b>Waste Weir 100 ft. long—</b>					
Excavation hard and stony soil	..	C. Yd.	1,198		
Burnt brick in chunam	..	C. Ft.	586		
Burnt stone slabs	..	Sqr. Ft.	190		
Plastering with chunam	..	Sqr.	3-60		
Rough stone work, new for wing	..	C. Yd.	10		

A. GOVINDACHARI, J. UOS  
Executive Engi

## COORG FOREST DEPARTMENT.

## NOTICE.

The 11th April 1892.

Owing to severe cholera in Hunsur the auction of the right to collect Minor Forest Produce in the Government Forests in Coorg is postponed *sine die*.

G. H. FOSTER,  
Deputy Conservator.